



Caledonia Play installed the following add-ons:

A **Climbing Rock Wall** offering a unique way to access the tree deck structure with specially designed coloured rock climbing holds suitable for both hands and feet to use.

A **Freestanding Tumble Bar** allowing endless tumbling and gymnastic skills to be developed. Constructed from quality 12cm machine rounded timber, the pole is 2m long 0.6m of which is cemented into the ground. The tumble bar itself is made from stainless steel.

Climbing Ramp with Pull Rope

Scramble Net (1.2 x 2.5m)

Spiral Ladder - Made from quality stainless steel.

Caledonia Play also installed the following products:

A 25 m long **Flying Fox** was been stalled with a starting platform at one end and a compression spring system at the finish to ensure a safe, controlled ride to the end.

All timbers used have been pressure-treated and fitted with post saver sleeves to protect the section below ground level.

The main cross beams are metal and have a tensioning winch which ensures that the wire can be tightened as needed – the wire will inevitably stretch with use.

The carriage is made with stainless steel with nylon roller so will not rust and it is also enclosed so it will not blow or fall off the cable.

The final element that we installed is a **Family Basket Swing**.

The swing frame is extremely robust using larger poles than our standard swing frames in order to support the heavy basket. The basket, which is made with an internal galvanised steel ring, stainless steel chains and herculean rope, is of commercial standard quality and conforms to European Safety Standard EN1176.

Designed to be freestanding the Family Basket Swing does not need to be concreted in or anchored down.

All round timbers are pressure treated with non-arsenic based preservative salts and impregnated with wax, and, all square sawn timbers have been graded, dressed and planed with eased corners and treated with non-arsenic based preservative salts.

Services provided by client:

Access to water supply.

Clear access and parking for the delivery vehicles.

Access into the area at any point in the working day, (8.30-17.00).



Flying Fox System being installed